

**LAND CORNER RECORDED INSTRUMENT  
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>32</u> T. <u>11</u> N. R. <u>3</u> E. <u>X</u>		<u>E-11, E-12</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		_____
4. LOT NO. _____, RECORDED PLAT _____		_____
5. PRIVATE CLAIMS _____		_____

Saginaw County

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

2

I, Dwayne Scott, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October, 1976, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**E-11** Found 3" diameter iron pipe 6" above ground. Recovered by measuring from gov't corners to the North and West.

**E-12** Recovered 3" diameter concrete monument. Found with notes by Spicer Engineering, a survey firm in Saginaw Michigan. Also measured West from center of section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**E-11** 3" diameter iron pipe with 1/2" diameter iron pipe inside with plastic cap R.L.S. #12029 on top of it.  
 North 57.00' to S. bank stream  
 S.70°W. 28.45' 8" Elm P.K. & tag  
 S.25°W. 8.35' Twin 4" & 6" Elm P.K. & tag  
 N.31°E. 27.40' Twin 16" & 14" Maple P.K. & tag  
 S.37°E. 34.40' 16" Elm P.K. & tag

**E-12** 3" diameter monument  
 S.40°W. 43.25' 7" Elm Sp. & tag  
 S.17°E. 46.10' Twin 3" & 5" Elm Sp. & tag  
 N.48°E. 85.05' 4" Elm Sp. & tag

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO 12029

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO 12029