

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 46 PM '95

MICHAEL J. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in

SAGINAW

(County)

Located In:

Corner Code #

SWAN CREEK TOWNSHIP

- 1. Public Land Survey T 11N R 3E F-1
T 11N R 3E G-1
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Sheet Page 14

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Brian D Ferguson, in a field survey on December 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-1 No corner originally set. LCRC recorded in 1979, L. 4 Pg 69.

G-1 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1972, L. 1 Pg 254

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found 3/4" iron pipe w/cap #4699. Fits fence lines to the South. Replaced pipe with 3" Brass Disk. This monument is accepted as the best available evidence of the position of the corner.

G-1 Found 3/4" iron pipe and replaced with 3" Brass Disk. This monument is accepted as the best available evidence of the position of the original corner.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 3" Brass Disk
North, 7.74', Nail in E fce 6" wood post
S. 45° W., 20.57', Nail in NE fce 15" Poplar
South, 78.00', Nail E fce 30" Oak, Chest level
West, 69.05', F-13 T12N-R3E, 3" Brass Disk

G-1 3" Brass Disk in monument box
S. 75° W., 80.73', Nail in N fce 10" Juniper
S. 50° W., 107.73', Nail in N fce 18" Apple
S. 15W., 140.15', Nail in N fce 24" Ponderosa Pine
S. 02° E., 9.50', Ctr line E leg street sign
West, 119.23', G-13 T12N-R3E, 3" Brass Disk

Signed by Brian D Ferguson Date 12-27-95
Surveyor's Michigan License No. 26454

