

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 46 PM '95

REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

For corners in

SAGINAW

(County)

Located In:

Corner Code #/

SWAN CREEK TOWNSHIP

- 1. Public Land Survey T 11N R 3E H-1  
T 11N R 3E (I-1)  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Lib 7 Page 18*

Register of Deeds Stamp & File Number

I, Brian D Ferguson, in a field survey on December 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

H-1 No corner originally set, no LCRC's or recorded surveys tied to this corner.

I-1 Wood post set by J. Wampler, Deputy Surveyor 1822.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-1 Set 3" Brass Disk on Standard line equal distance from G-1 and I-1 This monument is accepted as the best available evidence of the position of the corner.

I-1 Found 3/4" iron pipe. Replaced with 3" Brass Disk. Monument is accepted as the best available evidence of the position of the original corner.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-1 3" Brass Disk in monument box West, 61.67', H-13 T12N-R3E, 3" Brass Disk N. 86° E., 23.06', Nail N fce 8" Elm N. 02° E., 20.07', Nail W fce 14" Maple N. 50° W., 11.58', Nail E fce 18" Maple

I-1 3" Brass Disk in monument box N. 85° W., 28.33', Fce light pole S. 50° E., 44.11', Top ctr hydrant West, 26.12', 3/4" iron pipe West, 34.94', I-13 T12N-R3E, 3" Brass Disk

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date 12-27-95

