

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

DEC 27 1 44 PM '95

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

BRUCE L. DODD
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in

SAGINAW
(County)

Located In:

Corner Code #/

JAMES TOWNSHIP

- 1. Public Land Survey T 11N R 3E J-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Lib 7 Page 12

Register of Deeds Stamp & File Number

I, Brian D Ferguson, in a field survey on December 18, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 No corner originally set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Set 3" Brass Disk on Standard line equal distance from I-1 and K-1 This monument is accepted as the best available evidence of the position of the corner.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 3" Brass Disk in monument box
N. 40° W., 39.20', Concrete monument
N. 45° E., 38.63', Nail & disk S fce pwr pole
East, 9.23', 3/4" pipe in Ctr line Jarabec Rd
West, 20.75', J-13 T12N-R3E, 3" Brass Disk



Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date 12-27-95