

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

12-7-94
For corners in Saginaw (County) SURVEY & REMONUMENTATION

MICHAEL J. BOGAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

Dec 29 9 28 AM '94

RECORDED & FILED

Located In: _____ Corner Code #/

1. Public Land Survey APR 24 1995 T 11N R 3E _____ K-1
 _____ T _____ R _____
 _____ T _____ R _____
 _____ T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Lib 1925 Page 273
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Duane F. Ledy, in a field survey on July 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-1 Set post at intersection with township line 19 links (12.54') east of K-13, J. Wampler, 1822.
 12" Elm N 57° W 5 links
 7" Ash S 55° E 22 links
 Saginaw County Surveyor, H. Cary, witnessed corner in 1876, 19 links east of K-13.
 Hammond found 3/4" pipe, 1979, L.C.R.C.: L5, P5.
 Leach found 3/4" pipe, 1980: L1586, P185.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-1 Found 3/4" pipe in monument box.
 Found recorded witnesses as follows:
 West 9.21' to S.W. corner Sec. 36 (K-13)(9.03'R).
 N.E. 43.85' to nail & tag in south face P.P. (43.92'R).
 S.E. 52.78' to top of fire hydrant (52.95'R).
 Existing monument accepted as best possible position of original corner.
 Existing monument accepted by Saginaw County Peer Review Group on December 7, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-1 Replaced 3/4" pipe with 3" Saginaw County brass cap in monument box.
 N 45° E 43.82' to nail and tag in utility pole.
 S 45° W 57.64' to nail and tag in utility pole.
 S 45° E 47.61' to nail and tag in utility pole.
 N 70° E 150.45' to PK nail in utility pole.
 West 9.21' to Saginaw County Remonumentation cap (K-13).



Signed by Duane F. Ledy Date December 28, 1994
 Surveyor's Michigan License No. 21575