

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>11</u> T. <u>11</u> N. S., R. <u>4</u> E. W.		J-5, K-4
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Saginaw Co

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

J-5 S½ Cor. Sec. 11 Found 1½" pipe.	K-4 E½ Cor. Sec. 11 Found iron in mon. box.
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5 S½ Cor. Sec. 11 1½" pipe at top of bank on West edge of ditch. S45°W - 1.25' - 6" Oak S10°W - 13.87' - 10" Ash N28°W - 14.24' - 8" Ash S80°W - 41.40' - 15" Ash Spikes & ref. tags in trees.	K-4 E½ Cor. Sec. 11 Iron in mon. box 2' west of g M-13 S70°W - 43.17' - Guy Pole West - 64.70' - Face of 4" dia. steel gate pos N30°W - 75.40' - Face of 3" dia. steel sign pos
---	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 2-29-84
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

