

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

LIBER 2028 PAGE 443

1997 OCT -3 A 8:28

MILDRED H. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in: FRANKENMUTH TWP.

SAGINAW (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>06E</u>	<u>M-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Seen 7 Aug 188
Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 GLO; WAMPLER, D.S.; SET POST; BEECH 30 N79E 25 LKS., SUGAR 6 N78W 9 LKS.
1972 DORCEY, LS#9429; LCRC DENMARK TWP. PG.4; FND. MON. BOX; NO WITS GIVEN
1972 MARTIN, LS#4699 LCRC L.1, PG.216; 3/4" IRON BAR; NE 38.77' P.POLE, SW 37.91' P.POLE, SE 13.90' SW COR CONC. WINGWALL, NE 24.12' NW COR. CONC. WINGWALL
1976 MARTIN, LS#4699 LCRC L.3, PG.179; 3/4" BAR IN MON. BOX; N45E 38.92' P.POLE, S45W 38.05' P.POLE, S45E 13.90' SW COR CONC. WINGWALL, N35E 24.12' NW COR. CONC. WINGWALL
1981 LEACH, LS#7236; LCRC L.5, PG.151; FND. 3/4" BAR IN MON. BOX; 38.92' P.POLE, N35E 26.2' CTR OF CMP, NW 85.50' PHONE RISER, S45W 38.05' P.POLE
1996 DUNTON, PS#23503; 1996 REMONUMENTATION LCRC TUSCOLA TWP. PG. 78; FND 7/8" BAR IN MON. BOX REPLACED W/ TUSCOLA CO. MONUMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. TUSCOLA COUNTY MONUMENT IN MON. BOX; RECOVERED ALL 1996 REMON WITNESSES

ACCEPTED FND. MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-1 TUSCOLA CO. MONUMENT IN MON. BOX
S52°E, 26.52' CHIS. NOTCH IN S. END CSP
N42°E, 32.61' CHIS. NOTCH IN N. END CSP
S44°W, 39.62' NAIL W/REMON TAG IN SE FACE T.POLE
N76°W, 84.80' NAIL W/REMON TAG IN S. FACE P.POLE
N58°E, 59.64' NAIL W/REMON TAG IN S. ROOT 40" COTTONWOOD
N63°E, 39.05' NAIL W/REMON TAG IN S. FACE T.POLE



Signed by Jonathan M. Field Date 9-25-97
Surveyor's Michigan License No. 37276

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

MAR 18 1998

REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

SECTION