

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

8-28-97

1997 OCT -3 A 8:27

For corners in: FRANKENMUTH TWP.

MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY, MI.

<u>SAGINAW</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>06E</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 2028 PAGE 430

*Slider 7 Page 175*

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1821 GLO; WAMPLER, D.S.; LYNN 10 AT SEC. COR.  
1976 MARTIN, LS#4699 LCRC L.3, PG.179; SET 3/4" PIPE BTWN NE & SE SEC. CORNERS IN LINE W/ OCCUPATION LINE TO WEST; N01E 145.00' T.POLE, WEST 4.0' C/L BIT. N-S

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 ROWE; FIELD, PS#37276; FND. NO EVIDENCE OF MONUMENT AT CORNER POSITION; FND NO REMAINING WITNESSES; RE-ESTABLISHED CORNER POSITION BY SINGLE PROPORTION TO GLO DIST. & ON LINE BETWEEN M-1 & M-3 T11N-R6E

ACCEPTED AS A CAREFUL AND FAITHFUL RE-ESTABLISHMENT OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-2 SET 5/8" ROD W/ STD. REMON. CAP IN MON. BOX  
N40°W, 26.26' 1/2" ROD W/ CAP #37276  
N25°E, 24.17' 1/2" ROD W/ CAP #37276  
S30°E, 26.00' 1/2" ROD W/ CAP #37276  
S40°W, 39.05' 1/2" ROD W/ CAP #37276



Signed by Jonathan M. Field Date 9-25-97  
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971

REVISED MAY 14, 1973  
REVISED JAN, 1993  
ADAPTED FOR WORD PROCESSING MARCH, 1993

SURVEY &  
REMONUMENTATION

MAR 18 1998

SECTION