

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED
EIBER 2028 PAGE 438
1997 OCT -3 A 8:28

7-23-97
For corners in: FRANKENMUTH TWP.

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

<u>SAGINAW</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>06E</u>	<u>M-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Side 7 Page 183
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 GLO; WAMPLER, D.S.; NOT SET; "BALANCE OF THIS MILE & SEC. 24 & 13 & PART OF 12 IN RESERVATION"
1839 GLO; MULLETT, D.S.; SET 1/4 SEC. POST; BEECH 12 S23W 16LKS., LYNN 7 N82W 36LKS.
1981 LEACH, LS#7236; LCRC L.5, PG.148; FND 3/4" ROD RAISED W/ 1" PIPE; SW 126.72' 24" MULBERRY, N45W 18.00' P-K IN BLACK TOP, WEST 14.00' P-K IN BLACK TOP, NORTH 189.63' T-IRON AT A-8 T11N-R7E, EAST 2' E. EDGE OF BLACK TOP
1986 R/C ENG.; FERGUSON, LS#26454; SURVEY L.1699, PG.1445-6; 1" PIPE; SW 126.0' 30" TREE, N. 190.0' A-8 T11N-R7E
1989 R/C ENG.; FERGUSON, LS#26454; SURVEY L.1891, PG.70; 1" PIPE W/CAP; SAME WITS AS 1981 LEACH SURVEY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. 1" PIPE 8' E. OF C/L REESE ROAD; RECOVERED 3 PREVIOUS WITNESSES WHICH INDICATE THAT FND. PIPE IS IN SAME POSITION AS 1981 LEACH LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND. PIPE AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-8 REPLACED FND. PIPE W/ 5/8" ROD & STD. REMON. CAP IN MON. BOX
NORTH, 189.72' BOAT SPIKE
N50°W, 18.10' P-K NAIL
N88°W, 18.25' 1/2" ROD W/CAP #37276
S12°W, 126.21' NAIL W/TAG #37276 IN E. FACE 30" TREE
S05°E, 29.95' 1/2" ROD W/CAP #37276



Signed by Jonathan M. Field Date 9-25-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1978
REVISED MAY 14, 1983
ADAPTED FOR WORD PROCESSING MARCH, 1988

SURVEY &
REMONUMENTATION

MAR 18 1998

SECTION