

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED
LIBER 2028 PAGE 435

1997 OCT -3 A 8: 28

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

For corners in: FRANKENMUTH TWP.

<u>SAGINAW</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>06E</u>	<u>M-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 7 Page 180

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JONATHAN M. FIELD, in a field survey on JULY 8 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1821 GLO; WAMPLER, D.S.; SET POST; SUGAR 9 N44W 13LKS., BEECH 16 S33W 45LKS.
 1958 BLACK, LS#3384; WIT CARD FOR A-11 T11N-R7E SHOWS NORTH 57.2' FROM SAGINAW CO. IRON
 1968 CPCO; WIT CARD; FND. 1" IRON ROD; S. OF C/L ORMES RD., NE ROAD SIGN
 1978 PREVOST, LS#24612; LCRC TUSCOLA TWP. PG.38; WITS FOR A-11 T11N-R7E SHOW SOUTH 56.97' TO 3/4" BAR AT M-11 T11N-R6E
 1981 DUNTON, LS#23503; SURVEY L.515, PG.940-941; WITS FOR A-11 T11N-R7E SHOWN SOUTH 124.76' 1" IRON AT M-11 T11N-R6E
 1981 LEACH, LS#7236; LCRC L.5, PG.151; FND. 3/4" ROD; NORTH 57.00' ROD AT A-11 T11NR-7E, S80E 9.25' PHONE RISER, N10E 58.65' ST. SIGN POST, N25E 7.90' N. LEG SIGN POST
 1982 LEACH ENG.; LEACH, LS#7236; SURVEY L.1608, PG.1940; FND. 3/4" ROD; SAME WITS AS 1981 LCRC ABOVE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 ROWE; FIELD, PS#37276; FND. 1" ROD IN MON. BOX AT C/L REESE ROAD & C/L CURTIS ROAD; RECOVERED 2 PREVIOUS WITNESSES WHICH INDICATE THAT FND. ROD IS IN SAME POSITION AS 1981 LEACH LCRC CITED IN SECTION A. ABOVE

ACCEPTED FND. ROD AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-11 SET 5/8" ROD W/ STD. REMON CAP OVER FND. 1" ROD IN MON. BOX
 NORTH, 124.81' 1/2" ROD W/CAP #23503
 NORTH, 57.17' 5/8" ROD
 S80°E, 9.25' PHONE RISER
 S45°W, 31.98' 1/2" ROD W/CAP #37276
 N45°W, 54.81' 1/2" ROD W/CAP #37276
 N50°E, 6.69' N. EDGE OF N. SIGN POST LEG



Signed by Jonathan M. Field Date 9-25-97
 Surveyor's Michigan License No. 37276

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1995
 REVISED MAY 14, 1995
 ADAPTED FOR WORD PROCESSING MARCH, 1995

MAR 18 1998

SECTION