

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

1997 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED/FILED

LIBER 2028 PAGE 433
1997 OCT -3 A 8:28

For corners in: FRANKENMUTH TWP.

SAGINAW (County)	Located In:	Corner Code #
1. Public Land Survey	T 11N R 06E	M-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MILDRED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY, MI.

Liber 7 Page 178

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, JONATHAN M. FIELD, in a field survey on JULY 8 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1821 GLO; WAMPLER, D.S.; SET POST; BEECH 30 N35E 2LKS., MAPLE 7 S13E 29LKS.
1887 GOODALE, C.S.; SURVEY OF SEC. 1&12 T10N-R6E, PG. 232; STONE; NO WITS GIVEN
1968 CPCO; BOLDT; FND. 1" ROD; NW 38.44' RD. SIGN, SE 59.39' POLE, SW 74.84' POLE
1978 PREVOST, LS#24612; LCRC TUSCOLA TWP. PG.38; FND. T-IRON; N45W 38.64' T.POLE, N44W 38.10' ST. SIGN POS
S45W 74.52' P.POLE, S40E 58.97' P.POLE, S45E 43.03 ST. SIGN POST
1980 SPICER ENG.; MARTIN, LS#4699; SURVEY L.505, PG.132-133; T-IRON; SAME WITS AS 1978 LCRC
1981 DUNTON, LS#23503; SURVEY L.515, PG.940-941; A-13 T11N-R7E SHOWN; NO OBJECT STATED; NO WITS GIVEN
1981 LEACH, LS#7236; LCRC L.5, PG.151; FND. T-IRON; S60E 43.0' ST. SIGN POST, S25E 59.05' PHONE RISER, N60W
38.80' TAG IN P.POLE, S45W 74.10' TAG IN P.POLE
1993 SPICER ENG.; PREVOST, PS#24612; SURVEY L.671, PG.1182; T-IRON; SAME WITS AS 1978 LCRC ABOVE
1994 ROWE ENG.; FIELD, LS#37276; 1994 REMONUMENTATION LCRC TUSCOLA TWP. PG.54; FND. T-IRON REPLACED
W/TUSCOLA CO. MONUMENT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 ROWE; FIELD, PS#37276; FND. TUSCOLA COUNTY MONUMENT IN MON. BOX AND ALL 1994 WITNESSES

ACCEPTED FND. MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 TUSCOLA CO. MONUMENT IN MON. BOX
N49°E, 30.15' 1/2" ROD
S29°E, 35.12' ROAD SIGN POST
S32°E, 59.43' NAIL W/DISK IN SW FACE P.POLE
S47°W, 74.05' NAIL W/DISK IN NW FACE P.POLE
S47°W, 74.86' CENTER OF CUT-OFF P.POLE
N50°W, 38.78' NAIL W/DISK IN NE FACE CUT-OFF P.POLE
N43°W, 38.41' ROAD SIGN POST



Signed by Jonathan M. Field Date 9-25-97
Surveyor's Michigan License No. 37276

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN.

SURVEY &
REMONUMENTATION

REVISED MAY
REVISED JA
ADAPTED FOR WORD PROCESSING MAR

MAR 18 1998

SECTION