

BR 8-31-94

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Lib 6 Page 212

For corners in **SURVEY &
 REMONUMENTATION**

Saginaw
 (County)

Located In:

Corner Code #

1. Public Land APR 24 1995 T 12N R 2E M 5
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

COMMISSION

RECORDED FILED

Nov 28 10 23 AM '94

MILDRED WOODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Craig W. McVean, in a field survey on June 21, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M 5 Set Post J. Wampler - 1822.
 Ash 20" South 12 Lks.
 Pine 18" N 46° W 17 Lks.

Recorded Surveys - L. 1344, P. 548 - 1971; L. 1469, P. 1267 - 1976; L. 1513, P. 102 - 1977; L. 1555, P. 369 - 1978; L. 1561, P. 302 - 1979; L. 1578, P. 1964 - 1979; L. 1578, P. 1964 - 1979; L. 1582, P. 1159 - 1980; L. 1592, P. 754 - 1980; L. 1681, P. 392 - 1986; L. 1803, P. 2242 - 1991.

SCRC witness card - iron post 6" below road - 1926.
 LCRC - L. 1, P. 67 - Found 3/4" pipe - Leach - 1971.
 SCRC witness card - 3/4" iron pipe - 1979 - place mon. box - 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M 5 Standard corner common to Section 12 and 13, T12N, R2E - Found 3/4" internal diameter (1" outer diameter) iron pipe in mon. box per SCRC, LCRC, and recorded surveys at N. edge of Frost Road. Agrees with GLO distance S. to A 5-T12N-R3E. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M 5 Replace 3/4" I.D. x 12" iron pipe with 2-1/2" Saginaw County brass cap on 5/8" rebar in mon. box.
 S 45° E (-R) 45.13' (44.95' - SCRC) to Found Nail and shiner in SW. side U.P.
 N 63° E 29.23' to capped 3/8" rebar.
 S 21° W 106.25' to nail and tag in E. side 12" box elder.
 S 13° E 74.70' (74.56' - SCRC) to set nail and tag in W. side U.P.
 N 45° W 39.48' to pk and tag in 12" CMP.
 South 19.91' (19.82' & 19.90'-R, 19.80' SCRC and GLO) to A 5-T12N-R3E.



Signed by Craig W. McVean

Date 11-16-94

Surveyor's Michigan License No. 39088