

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Spec 6 Page 205

For corners in

**SURVEY &
REMONUMENTATION**

Saginaw

Located In:

Corner Code #

RECORDED & FILED

1. Public Land Survey **APR 24 1995** T **12N** R **2E** **M 9**
T _____ R _____
T _____ R _____
T _____ R _____
COMMISSION _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 28 10 22 AM '94

MILLEN, M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on July 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M 9 Set Post - J. Wampler - 1822.
Ash 7" S 16° E 20 L.
Lynn 6" N 84° W 4-1/2 L.

LCRC - L. 5, P. 140 - Field note of 1957 showed 35.5' between NW corner Section 30, T12N, R3E and NE corner Section 25, T12N, R2E - However no corner was actually at NE corner 25 - Set 3/4" pipe from evidence observed in 1957 notes - Prevost - 1981.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M 9 Standard Section corner common to Section 24 and 25, T12N, R2E - Found 3/4" I.D. iron pipe per record LCRC in line with S. bank of drain from the West. Found recorded witnesses as follows:
S 45° E (R) 42.5' (42.60'-R) to face 36" (30"-R) maple.
S 65° E (R) 71.05' (71.15'-R) to face P.P.
South 35.5' R&M to NW corner Section 30, T12N, R3E.
Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M 9 Replace 3/4" pipe with 2-1/2" Saginaw County brass cap on 5/8" x 18" rebar in mon. box.
S 60° E 71.44' to set nail and tag in S. side U.P.
East 21.83' to chiseled "x" on E. end 48" RCP.
N 10° E 100.90' to nail and tag in E. side 18" ash.
N 70° W 23.97' to chiseled "x" on W. end 48" RCP.
South 35.50' to A 9-T12N-R3E.



Signed by Craig W. McVean
Surveyor's Michigan License No. 39088

Date 11-17-94