

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

Saginaw County Remonumentation

LIBER 1922 PAGE 1843

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sheet 6 Page 209

BWR 9-23-94

RECORDED & FILED

For corners in SURVEY &

REMONUMENTATION

Located In:

Corner Code #

1. Public Land Survey **APR 24 1995** T **12N** R **2E** **M 11**
 T _____ R _____
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Nov 28 10 23 AM '94

HILDRICH GOSAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on July 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M 11 Set Post - J. Wampler, 1822.

Ash 6" N 75° E 7 Lks.

Birch 14" S 75° W 33 Lks.

LCRC - L. 1632, P. 2018 - Found 1" pipe - Prevost - 1982.

SCRC witness card - Found 1" pipe - 4" below bituminous - no date.

Recorded Survey - L. 1636, P. 249 - 1984.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M 11 Standard corner common to Section 25 and 36, T12N, R2E - Found 1" internal diameter pipe per LCRC, SCRC, and recorded survey. Monument agrees with GLO closing N. to A 11-T12N, R3E. Monument accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M 11 Replace 1" internal diameter x 36" long iron pipe with 2-1/2" Saginaw County brass cap on 5/8" x 18" rebar in mon. box. North 22.81' (22.8'-R, 22.9'-SCRC, 22.44'- GLO) to A 11-T12N-R3E. S 80° E 67.94' (67.92'-R, 67.9'-SCRC) to NW corner of block foundation of brick House #1017. S 47° E 84.83' to SW corner of block foundation of brick House #1017. S 30° E 62.82' to nail and tag in W. side U.P. N 68° W 51.67' (51.75'-R and SCRC) to set nail and tag in N. side U.P. S 46° W 69.30' to face 6" steel gate post.



Signed by Craig W. McVean

Date 11-16-94

Surveyor's Michigan License No. 39088