

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY SURVEY & REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1924 PAGE 770

RECORDED
& FILED

DEC 14 4 07 PM '94

H. L. LUDAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

For corners in
 Saginaw (County) Located In: Corner Code #
 APR 24 1995
 1. Public Land Survey **COMMISSION** T 22N R 3E A-1
 T R
 T R
 T R
 2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Liber 6 Page 224

Register of Deeds Stamp & File Number

I, John H. Rauser, in a field survey on May 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7	8		9		10		11		12		
5													
6		18	17		16		15		14		13		
7													
8		19	20		21		22		23		24		
9													
10		30	29		28		27		26		25		
11													
12		31	32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A-1) Township Cor. common to T13N-R2E & 3E & T12N-R2 & 3E
 Wood post placed by J. Wampler, Deputy Surveyor 1822
 S31°W 16 lks (10.56') Sugar Maple
 N21°E 5 lks (3.30') Ironwood
 1920's Saginaw County Road Commission witnesses
 1974 Saginaw County Road Commission witnesses
 1991 Act 132 by Duane F. Ledy #21575, Rec. in L.1801, Pg.208, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A-1) Township Cor. common to T13N-R2E & 3E & T12N-R2 & 3E
 Found no evidence of original government corner.
 Found 3/8" rerod in Mon. Box
 as per L.1801, Pg.208, Saginaw County Records & 1974 Road Commission notes and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A-1) Township Cor. common to T13N-R2E & 3E & T12N-R2 & 3E
 Reset 5/8" rerod w/brass cap stamped Saginaw County Monument,
 P.S. #39096 in existing Monument Box.
 N37°W 40.02' End PK in SE fce PP
 N40°E 35.79' Set chis "+" in top center 12" cmp
 S35°W 48.21' Set spike w/tag #39096 NW fce PP
 N60°W 109.72' SW cor conc foundation garage on house #4492



Signed by John H. Rauser Date _____
 Surveyor's Michigan License No. 39096