

8-20-96 *Blf*

Sheet 7 Page 50

For corners in Thomas Township

Saginaw (County)	Located In:	Corner Code #
1. Public Land Survey	T 12 N. R 3 E.	B-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
 SEP 23 11 34 AM 1996
 RECORDED & FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 1-31, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- B-5 Post set by Wampler, 1822
- S.C.R.C. information, 1926
- Spicer Eng. Notes, 1958, Lag screw set
- L.C.R.C. L1 P191, 1972, McKelvey 1/2" Iron bar set
- Recorded surveys L1344 P579, L1349 P799, L1366 P168, L1485 P611 & L1511 P654

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-5 Found 1/2" rod in Mon Box
- South 52.07 (52.40R) face P. Pole (SEC 1958)
- South 52.30 (52.47R) nail & tag #19001 in P. Pole (LCRC L1 P191)
- North 31.49 (31.49R) nail & tag #19001 in P. Pole (LCRC L1 P191)
- North 31.10 (31.03R) face P & T Pole (Rec. Survey L1349 P799)
- South 52.30 (52.19R) face P. Pole (Rec. Survey L1349 P799)
- N.E. 102.28 (102.28R) SE cor. House (Rec. Survey L1349 P799)
- Location accepted by Peer Review Group 8-20-96 as the best available evidence of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-5 Replaced 1/2" rod with 5/8" rod & Saginaw Co. Re-Mon cap in existing Mon Box 9-96.
- S. 52.30 to nail & tag #19001 in P. Pole.
- N. 31.49 to nail & tag #19001 in P. Pole.
- N.45°E. 102.28 to S.E. cor. house
- S.45°W. 46.60 ctr. Water S.O. valve

Signed by Ronald C. Prevost

Date 9-20-96

Surveyor's Michigan License No. 24612



MAY 16 1997

COMMISSION