

APPROVED BY PEER GROUP SAGINAW COUNTY REMONUMENTATION
P.A. 345 OF 1990
SAGINAW COUNTY

11/29/95 *RCP*

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Liber 7 Page 27

For corners Saginaw
(County)

Located In: THOMAS TWP. Corner Code #

1. Public Land Survey	T	12 N.	R	3 E.	B-9
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
 DEC 28 12 36 PM '95
 RECORDED & FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Ronald C. Prevost Nov. 29 95
I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9	●											
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-9 Post Set by J. Wampler, 1822
L.C.R.C. L4 P248, 3/4" Pipe, Rowe Eng. 1978. 3/4" Pipe was set using data supplied by Spicer Eng., Spicer had accepted a fence corner location previously (1958)
Recorded Survey L1580 P1166
LCRC Witnesses N.10°E. 7.75 found 3/4" Pipe
S.20°E. 34.30 RLS Tag 11192 in 10" Maple
S.10°W. 13.45 RLS Tag 11192 in 10" Maple

CORNER
REMONUMENTATION
FEB 22 1996
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9 Found 3/4" Pipe as Recorded in L4 P248
All witnesses existing and check
No knowledge of who set 3/4" Pipe N.10°E. 7.75' Suspect
It could have been Dow Chemical surveyors.
Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co Peer Group 11-20-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 Set 3" x 36" Steel Pipe filled with concrete with 5/8" Re-Rod and Saginaw County Brass Cap in place of previously recorded 3/4" pipe. 12-4-95.
S.20°E. 34.30 RLS tag 11192 in 10" Maple.
S.10°W. 13.45 RLS tag 11192 in 10" Maple.
S.03°E. 16.90 Face 10" Oak
N.40°W. 5.35 Face 30" Maple (Triple)
N.60°W. 7.40 Face SE'ly 12" Oak in clump of four.



Signed by *Ronald C. Prevost*

Date 12-27-95

Surveyor's Michigan License No. 24612