

Review Page 29

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9/28/95 RCF
For corners in Saginaw
(County)

Located In: Thomas Twp.
Corner Code # _____

RECORDED & FILED
DEC 28 12 36 PM '95
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

	12 N. 3 E.		C-10
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ronald C. Prevost Sept. 28 95

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-10 Post Set by Wampler, 1822
- L.C.R.C. L1, P145, Iron Rod, 1971, Sides
- L.C.R.C. L1, P178, 3/4" Spike, 1972, McKelvey
- L.C.R.C. L3, P189, RR Spike head broken off, 1976, Martin
- + in Pvt 1947, J.W. Martin (Spicer)
- Recorded surveys L1362 P1032, L1518 P186, L1567 P1217

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-10 Set nail from witnesses by Spicer Eng. and recordings.
- See record witnesses that agree in Section C.
- Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co. Peer Group 9-28-95

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-10 Placed 5/8" Re-rod, Saginaw County Brass Cap & Mon. Box 10-11-95
- S.45°W. 74.30 NE Corner Blk. Foundation (74.23 R)
- S.60°W. 88.25 NW Corner Blk. Foundation
- S.40°E. 63.52 Nail & Cap NW face T. Pole, Sect. (63.46 R)
- N.45°E. 44.65 Nail & Cap SW Face P & T Pole, Sect. (44.9 R) (44.46 R)
- N.50°W. 61.50 Nail & Cap SE Face P & T Pole, Sect. (62.90 R) (62.31 R)
- N.40°E. 52.40 Ctr. Hyd.



Signed by Ronald C. Prevost
Surveyor's Michigan License No. 24612

Date 12-27-95