

DEC 14 4 06 PM '94

MICHAEL J. BODAK REGISTER OF DEEDS SAGINAW COUNTY MICH.

APPROVED BY PEER GROUP P.A. 345 OF 1990

SAGINAW COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

8-31-94 [Signature]

For corners in Saginaw (County) SURVEY & REMONUMENTATION Located In: Corner Code #

- 1. Public Land Survey APR 24 1995 T 12N R 3E D-1
2. Property Controlling in Section COMMISSION S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Lib 6 Page 225

Register of Deeds Stamp & File Number

I, John Rauser, in a field survey on June 30, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked in cell D-1.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (D-1) N 1/4 Cor., Sec. 5, T12N-R3E Not set during original government survey 1970 7-2-70 Saginaw County Road Commission, Found 3/4" Iron Pipe 1970 9-14-70 Placed Mon. Box, Saginaw County Road Commission 1972 L.C.R.C. Gerald R. McKelvey, P.S. #19001, Rec. L. 1361, Pg. 1132-1133, Saginaw County Records. Act 132 by Gerald R. McKelvey, P.S. #19001, Rec. L. 1361, Pg. 217-218, Saginaw County Records. 1981 Act 132 Arthur H. Leach, P.S. #7236, Rec. in L. 1597, Pg. 217-218, Saginaw County Records. Act 132 by Ronald C. Prevost, P.S. #24612, Rec. L. 1606, Pg. 1521-1522, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (D-1) N 1/4 Cor., Sec. 5, T12N-R3E Found 3/4" iron pipe in Mon. Box with no cover. Checked within 0.2'± to stumps of reference trees as per records as stated in "A" above. This position not established by original government survey. This monument is accepted as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (D-1) N 1/4 Cor., Sec. 5, T12N-R3E Reset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096 in existing monument box. N43°E 33.86' Set 3/4" pipe w/cap #39096 in S ditch bank N side rd 12'± N of N edge of pvmt N79°E 100.09' S edge traffic sign S46°E 163.73' Set spike w/tag #39096 SW fce PP S30°E 69.14' Set spike w/tag #39096 W fce 6" apple tree East 44.34' D-13, T13N-R3E

Signed by John H. Rauser Date Jan. Surveyor's Michigan License No. 39096

