

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 46 PM '95

REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in

SAGINAW
(County)

Located In:

Corner Code #:

THOMAS TOWNSHIP

- 1. Public Land Survey T 12N R 3E
T 12N R 3E
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

D-13
E-13

Libert Page 15

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Brian D Ferguson, in a field survey on December, 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 Wood post set by J. Wampler, Deputy Surveyor 1822. SW Corner of DUDE ESTATES as recorded in L 22, Pge 27

E-13 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1978, L. 4 Pge 92. SE Corner of DUDE ESTATES as recorded in L 22, Pge 27

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found no evidence of original government corner. Found concrete monument per plat of DUDE ESTATES.

E-13 Found no evidence of original government corner. Found RR Spike in shoulder of road.

SURVEYOR'S
REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 3" Brass Disk in monument box N. 30° E., 45.08', Spike in W fce 14" Maple South, 42.92', Spike in W fce 16" Cottonwood S. 40° W., 69.22', Spike in E fce 16" Maple S. 35° E., 85.36', Spike in NE fce 8" Poplar East, 13.74', D-1 T11N-R3E, 3" Brass Disk

E-13 3" Brass Disk in monument box East, 26.45', E-1 T11N-R3E, 3" Brass Disk S. 85° W., 67.29', Nail & cap N fce pwr pole N. 75° W., 81.85', Nail & cap N fce pwr pole S. 85° E., 59.80', Top ctr hydrant S. 85° E., 93.40', W fce pwr pole

Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date 12-27-95

