

SAGINAW COUNTY REMONUMENTATION PROJECT

LAND CORNER RECORDATION CERTIFICATE

DEC 14 4 07 PM '94

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

For corners in

Saginaw

(County)

**SURVEY &
 REMONUMENTATION**

Located In:

Corner Code #

1. Public Land Survey	T 12N	R 3E	E-1
APR 24 1995	T	R	
	T	R	
	T	R	
2. Property Contained in Section	S	T	R
3. Miscellaneous Property in Sec.	S	T	R

Lib 6 Page 236

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5		4	3				2	1			
3													
4	7	8		9	10				11	12			
5													
6	18	17		16	15				14	13			
7													
8	19	20		21	22				23	24			
9													
10	30	29		28	27				26	25			
11													
12	31	32		33	34				35	36			
13													

I, John H. Rauser, in a field survey on May 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E-1) Closing Sec. cor, Sec 4 & 5, T12N-R3E
 Corner not set by J. Wampler during original 1822 government survey. Corner fell in Indian Reservation. Wood post set by J. Mullett, Deputy Surveyor during survey of Saginaw reserve, 1839.
 1972 Act 132 by Gerald R. McKelvey, P.S. #19001, rec. in L. 1362, pg. 1132-1133, Saginaw County Records.
 1972 L.C.R.C. by same, rec. in L. 1, pg. 171, Saginaw County Records.
 1974 Act 132 by Arthur H. Leach, P.S. #7236, rec. in L. 1434, pg. 903-905, Saginaw County Records.
 1978 Witnesses by Saginaw County Road Commission
 1978 Act 132 by John W. Martin, P.S. #4699, rec. in L. 1676, pg. 1481, Saginaw County Records.
 1981 Act 132 and L.C.R.C. by Ronald C. Prevost, P.S. #24612, rec. in L. 1606, pg. 1521-1522 & L. 5, pg. 170, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E-1) Closing Sec., cor., Sec. 4 & 5, T12N-R3E
 Found no evidence of original government corner. Found R/R spike 0.35' below asphalt surface in centerline of Tittabawassee Road, as per record as stated in "A" above. Record survey recorded in L. 1434, pg. 903 shows that corner position is consistent with the records of the original reservation survey by J. Mullett, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E-1) Closing Sec. cor., Sec. 4 & 5, T12N-R3E
 Raset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096 in centerline of Tittabawassee Road, Placed monument box flush w/pav't
 S44°E 50.28' End. spike N. fc. Power Pole
 S44°E 50.77' End. Nail w/large washer NE fc. Power Pole
 S41°E 46.83' End. rerod w/cap #26454
 N71°E 78.43' End. spike in NNW fc. Power Pole
 N15°W 30.26' End. spike w/flag E. fc. Power Pole stub
 East 24.23' E-13, T13N-R3E

Signed by John H. Rauser Date Jan 1994

Surveyor's Michigan License No. 39096

