

For corners in Thomas Township

Saginaw (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12 N.</u> R <u>3 E.</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED & FILED
 SEP 23 11 34 AM 1996
 MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
Liber 7 Page 48
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Ronald C. Prevost, in a field survey on 1-31, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3					●								
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-3 Post set by Wampler, 1822
 L.C.R.C. 1972, L1, P171, Bold in bridge deck, Rec'd by McKelvey
 All Witnesses gone, new bridge.
 Spicer Eng. Survey notes of 4-18-75 called for square head
 Bolt in bridge deck, all witnesses gone.
 Recorded surveys L1419 P380, 1974, L1612 P1976, 1982 & L1721 P242, 1987

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3 The bridge mentioned above has been removed and a new bridge is in place. The new bridge construction plans indicate and witness the bolt in old bridge deck. These witnesses along with previous Section corner ties to East & to West and a monument 259.29 feet East at Curve Road were used to set a point on the New Bridge Deck and all were in agreement.

Location accepted by Peer Review Group 3-6-96 as the best available evidence of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3 Set 5/8" Rod & Sag. Co. Re-Mon cap in bridge deck, top of cap slightly below deck surface so as not to be hit by plows and such 9-96.
 S80°E. 89.51' to lower bolt that anchors end of guard rail to bridge.
 N.70°E 89.83 to lower bolt that anchors end of guard rail to bridge.
 N.70°W. 46.26 to lower bolt that anchors end of guard rail to bridge.
 S.60°W. 45.44 to lower bolt that anchors end of guard rail to bridge.

Signed by Ronald C. Prevost

Date 9-20-96



Surveyor's Michigan License No. 24612

REMONUMENTATION
 MAY 1 6 1997
 COMMISSIONER