

APPROVED BY PEER GROUP SAGINAW COUNTY REMONUMENTATION

P.A. 345 OF 1990

SAGINAW COUNTY

LIBER 1956 PAGE 1123

Liber 7 Page 32

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

9/28/95 *RF*

For corners in Saginaw
(County)

Located In: Thomas TWP Corner Code #

RECORDED & FILED
DEC 20 12 36 PM '95
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

1. Public Land Survey	T	<u>12 N.</u>	R	<u>3 E.</u>	E-10
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Section	S		T		R
	S		T		R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Ronald C. Prevost, In a field survey on Sept. 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10 Post Set by Wampler, 1822
 L.C.R.C. L1 P145, 1971, Mon Box, Sides
 L.C.R.C. L4 P159, 1978, 3/4" Pipe Mon Box, Prevost
 Recorded Surveys L1506 P151, L1567 P1217
 1/2" Ø Pin Found by J.W. Martin (Spicer) 1947

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10 Found 3/4" Pipe in Mon Box
 2616.61 North to E-9 (2617.04R MDOT)
 Is accepted as the best available evidence of the position of the original corner.
 Ratified by Saginaw Co. Peer Group 9-28-95

REMONUMENTATION
 FEB 22 1996
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10 Replaced 3/4" Pipe with 5/8" Re-Rod and Saginaw Co. Brass Cap in existing Mon Box. 11-28-95
 N.65°E. 58.62 Nail & Cap in Face SW Face P & T Pole
 N.45°W. 67.74 Nail & Cap in Face SE Face P & T Pole (66.43 Face R)
 N.65°E. 90.35 Ctr. Hyd. (90.51R)
 S.40°E. 58.55 Ctr. M.H.



Signed by *Ronald C. Prevost*

Date 12-27-95

Surveyor's Michigan License No. 24612