

DEC 14 4 07 PM '94

MICHAEL J. JOAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

APPROVED BY PEER GROUP
P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
SAGINAW COUNTY
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9-23-94 [Signature]

For corners in
Saginaw (County) **SURVEY & REMONUMENTATION** Located In:

Corner Code #

- 1. Public Land Survey T 12N R 3E
APR 24 1995 T R
T R
T R
T R
- 2. Property Controlling in Section COMMISSION S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

F-1

Lib 6 Page 235

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, John H. Rauser, in a field survey on May 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F-1) N 1/4 cor., Sec. 4, T12N-R3E
 Not set during original government survey.
 1967 Plat of Indian Reserve Acres, rec. in L. 16, pg. 38, Saginaw County Records.
 1972 L.C.R.C. by John W. Martin, P.S. #4699, rec. in L. 1, pg. 258, Saginaw County Records.
 1974 Act 132 by Arthur H. Leach, P.S. #7236, rec. in L. 1434, pg. 903-906, Saginaw County Records.
 1978 Act 132 by John W. Martin, P.S. #4699, rec. in L. 1676, pg. 1481, Saginaw County Records. Witnesses by Saginaw County Road Commission
 1981 Mon. Box placed by Saginaw County Road Commission.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-1) N 1/4 cor., Sec. 4, T12N-R3E
 Found 3/4" pipe in mon. box as per record as stated in "A" above. This position not established by original government survey. This monument is accepted as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-1) N 1/4 cor., Sec. 4, T12N-R3E
 Reset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096 in existing Monument Box.
 N51°E 71.93' Set PK w/tag #39096 in SE fc. new Power Pole
 S32°E 61.34' End. Spike in E. fc. Utility Pole
 S32°E 60.92' End. PK in NE fc. Utility Pole
 S22°W 41.49' End. Spike in S. fc. Guy Pole
 S22°W 41.06' End. PK in NW fc. Guy Pole
 East 51.85' F-13, T13N-R3E

Signed by John H. Rauser Date _____
 Surveyor's Michigan License No. 39096

