

APPROVED BY PEER GROUP  
P.A. 345 OF 1990

SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

10-23-96

For corners in

THOMAS TWP

Saginaw  
(County)

Located In:  
Thomas Twp.

Corner Code #

1. Public Land Survey

T12N R 3E	E-7
T12N R 3E	F-5
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECORDED & FILED  
OCT 31 2 23 PM 1996  
MILDRED H. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Duane F. Ledy, in a field survey on October 25, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5						⊙							
6		18		17		16		15		14		13	
7						⊙							
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-7  
Set post at 39.77 chains West of G-7; 1822, Joseph Wampler  
9" Sugar-S71°W, 9 links  
12" Sugar-S49°E, 6 links

L.C.R.C. Martin (L1, P257) 1972 3/4 Pipe.  
Surve-Martin (L1376, P1288) 1972 3/4" Pipe.  
Survey-Ledy (L 1783, P2069) 1990 1/2 Rod in Mon Box.

F-5  
Set post at 39.82 chains West of G-5; 1822, Joseph Wampler  
40" Pine-West, 3 1/2 links  
9" Beech-N3°E, 9 1/2 links

L.C.R.C.-Martin (L2, P107) 1973 P.K. nail.  
Survey -Martin (L1376, P1288) 1972 P.K. nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 Found 1/2" Rod (leaning) in Mon. box.  
L.C.R.C. & Survey by Martin witness:  
E 48.44' (47.38' measured 6' high) Fce P. P.  
SE 107.69' (107.35' m) to angle point on E. end of N. abutment.  
Survey by Ledy witness:  
NE 41.90' (41.88 m) to spike in 6" Maple  
E. 47.76' (47.75' m) to P.K. nail in P.P.  
SE 37.33' (37.35' m) to P.K. in Top Guard Rail Post  
SW 34.50' (34.58' m) to P.K. in Top Guard Rail Post

Monument accepted as best evidence of original position.

F-5 Found 3/4" pipe in Mon box.  
L.C.R.C. & Survey witness:  
N 28.41' (28.60' m) Fce P. & T. P.  
SE 54.42' (54.45' m) Fce P. P.  
NW 73.60' (73.74' m) Ctr Fire Hyd.

Monument accepted as best evidence of original position.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7  
Set 5/8" rod with remon. cap in monument box.  
SW, 34.58' to PK in top, North end guard rail post  
SE, 37.35' to PK in top, North end guard rail post  
East, 47.75' to PK in S side P.P.  
NE, 41.88' to nail in SE side 8" Maple

F-5  
Set 5/8" rod with remon. cap over 3/4" pipe in monument box.  
N, 28.89' to nail & tag in P.P. 1.5' above ground  
NW, 73.74' to top centerline fire hydrant  
SW, 50.15' to gas pipeline marker  
SE, 54.61' to nail & tag in W side P.P.  
West, 30' to centerline of Lone Road to North

Signed by Duane F. Ledy  
Surveyor's Michigan License No. 21575

Date \_\_\_\_\_



MAY 16 1997