

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LIBER 1956 PAGE 1124

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Sheet 1 Page 33

11/29/95
 For corners in Saginaw

Located In: *Thomas Twp.*
 Corner Code #

RECORDED & FILED
 DEC 28 12 36 PM '95
 REGISTER OF DEEDS
 SAGINAW COUNTY, MICH.

	12 N.	3 E.	F-9
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Section	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Ronald C. Prevost Nov. 29 95
 I, _____, in a field survey on _____, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 Post Set by Wampler, 1822
 Location established in 1972, accepted fence corner.
 3/4" Pipe set at fence corner location in 1973, J.W. Martin.
 L.C.R.C. L4 P54, 3/4" Pipe, 1977, J.W. Martin

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found 3/4" Pipe using L.C.R.C. Data, L4 P54
 Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co. Peer Group 11-29-95

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Replaced 3/4" Pipe with 3" x 36" Steel Pipe filled with concrete with 5/8" Re-Rod and Saginaw County Brass Cap 12-5-95.
 S.85°W. 27.61 Nail & Cap in Face 18" Oak (28.0R)
 N.02°E. 32.73 Nail & Cap in Face 6" Pine
 East 49.30 Nail & Cap in Face 38" Elm
 North 2617.07 3/4" Pipe at F-8



Signed by *Ronald C. Prevost*
 Surveyor's Michigan License No. 24612

Date *12-27-95*