

RECORDED  
&  
FILED

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

DEC 27 1 44 PM '95

12/6/95 *BDF*

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MICHAEL J. DUDAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

For corners in

SAGINAW  
(County)

Located In:

Corner Code :#

THOMAS TOWNSHIP

- 1. Public Land Survey
  - T 12N R 3E
  - T 12N R 3E
  - T \_\_\_\_\_ R \_\_\_\_\_
  - T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec.
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
  - S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

F-13  
G-13

*Side 7 Page 11*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Brian D Ferguson, in a field survey on December, 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1977 in L 4, Pg 55

G-13 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1971, L. 1 Pg 90. All witnesses gone

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found no evidence of original government corner. Found 3/4" pipe

G-13 Found no evidence of original government corner. Set 3" brass disk at average location of re-tracement of 4 different survey by 4 different surveyors.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 3" Brass Disk  
East, 69.05', F-1 T11N-R3E, 3" Brass Disk  
North, 50.53', Spike E fce 15" Poplar  
N. 60° W., 16.05', Spike S fce 6" Poplar  
S. 40° W., 67.18', Spike E fce 30" Oak

G-13 3" Brass Disk  
East, 119.23', G-1 T11N-R3E, 3" Brass Disk  
West, 39.55', E fce 6" steel gate post  
S. 35° E., 48.53', Spike N fce 8" Cedar  
N. 15° W., 12.50', Spike E fce 10" Pine

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date 12-27-95

