

APPROVED BY PEER GROUP
P.A. 345 OF 1990

LIBER 1989 PAGE 2284

Liber 7 Page 110

SAGINAW COUNTY SAGINAW COUNTY REMONUMENTATION

10-23-90 *BJF* LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Saginaw (County) THOMAS TWP
Located In: Thomas Twp. Corner Code #

1. Public Land Survey	T12N R 3E	<u>G-6</u>
	T12N R 3E	<u>G-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED & FILED
OCT 31 2 23 PM 1990
HILDAED M. DODAK
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Duane F. Ledy, in a field survey on October 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3												
4	7	8			9		10		11		12	
5												
6	18	17			16	<u>G-6</u>	15		14		13	
7						<u>G-7</u>						
8	19	20			21		22		23		24	
9												
10	30	29			28		27		26		25	
11												
12	31	32			33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6
Set post at 40.00 chains North of G-7; 1822, Joseph Wampler
18" Beech-S71°W, 9 links
11" Elm-N7 1/2°W, 33 links

G-7
Set post at 80.00 chains North of G-9; 1822, Joseph Wampler
44" Elm-S28°W, 35 links
32" W. Oak-N9°E, 29 links
L.C.R.C.-Prevost (L4, P217) 1979 Found large pointed stone & old rotted post, set 3/4" pipe to more closely define corner during a 1975 survey.

No L.C.R.C. of record.

Survey - Ledy (L1783, P1228) 1990 Found 3/4" Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6
Found 3/4" Pipe 4' East of W. Edge Bit. over 1/2" x 3" bar 2' deep.
West 54.35' (54.30' m) to Spike in P.P.
SW 38.81' (38.78' m) to Spike in 10" Ash
NNW 77.13' (77.10) to Spike in 8" Scotch Pine

G-7
Found 3/4" Pipe/Cap #4699
N 6.2' (6.6' m) to Fce 12" Twin Alder
In line with fence to North.

Only witnesses available.

Monument accepted as best evidence of original position.

Monument accepted as best evidence of original position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6
Set 5/8" rod with remon. cap over 1/2" x 3" bar.
West 54.27' to Nail in N side Power Pole
NNW 77.11' to Nail in W side 10" Pine
NNE 46.72' to Nail in 10" Elm
SW 38.74' to Nail in NW side 10" Ash
SSW 85.06' to Nail in E side 12" Pine

G-7
Set 5/8" rod with remon. cap over 3/4" pipe.
North 6.66' to nail in E side 14" Twin Ash
East 0.58' to PK in S side Fence Post
South 13.76' to nail in E side 6" Ash
SW 9.70' to nail in E side 4" Elm

Signed by Duane F. Ledy
Surveyor's Michigan License No. 21575

Date 10/31/96



MAY 1 8 1997