

APPROVED BY PEER GROUP  
P.A. 345 OF 1990

SAGINAW COUNTY SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

10-23-96 *[Signature]*

For corners in

THOMAS TWP

Saginaw  
(County)

Located in:  
Thomas Twp.

Corner Code #

1. Public Land Survey

T12N R 3E G-8

T R

T R

T R

T R

T R

T R

T R

2. Property Controlling  
in Section

S

S

S

S

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Duane F. Ledy, in a field survey on October 30 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

RECORDED & FILED  
OCT 31 2 23 PM 1996  
MILDRED M. DODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.  
Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21	⊕	22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-8

Set post at 40.00 chains North of G-9; 1822, Joseph Wampler

12" Beech-S25°W, 8 links

8" Beech-N11 1/2°E, 21 links

-L.C.R.C. by McGinnis (L2, P197) 1973 Calls for 1/2" iron, no mention of whether found or set.

-Survey by McGinnis (L1382, P592) 1972 calls for found iron with witness same as that for L.C.R.C. (L2, P197)

-Survey by Hammond (L1540, P642) calls for same 1/2" iron and witnesses as McGinnis.

-L.C.R.C. by Prevost calls for 3/4" pipe per 1958 survey notes from Spicer Engineering company. He also mentions finding the 1/2" "rod" per McGinnis. Prevost notes that 1/2" rod may be from stakeout of Swan Valley Golf Sub.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-8

Found 1" Pipe at point of 3/4" pipe per Prevost witness. Pipe was 3' long with broken pottery around it.

Remaining witnesses were:

NW 107.4' (107.11' m) to SE Cor. Block Foundation Hse.

SE 66. 83' (66.85' m) to Face Pole "New pole since 1958"

Witness spikes in trees used for L.C.R.C. (L2, P196) were found but 1/2" iron per McGinnis was not found.

The found 1" pipe was accepted as best available evidence of original position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-8

Set 5/8" rod with remon. cap in monument box.

North 29.80' to Nail in West side 52" Oak

SE 29.51' to Nail in NE side 8" Oak

NE 55.55' to Spike in SE side 30" Maple

SW 87.78' to Nail in SE side 8" Birch

Signed by Duane F. Ledy  
Surveyor's Michigan License No. 21575

Date 10-31-96



MAY 16 1997

COMMISSION