

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Saginaw

(County)

Located In:

Corner Code #

12 N. 3 E. G-9

1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

Sheet 7 Page 34

REGISTERED & FILED
SAGINAW COUNTY MICH.

Dec 28 12 36 PM '95

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Ronald C. Prevost Nov. 29 95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9 Post Set by Wampler, 1822
3/4" Pipe set by J.W. Martin (Spicer) in 1946 at remains of wood stake which was located with County Eng's Office Data.
Rec'd surveys L1382 P587, L1523 P843, L1540 P642
L.C.R.C. L3 P76, 3/4" pipe, 1974, J.W. Martin
Mon Box set over 3/4" pipe by Sag. Co. Rd. Comm. in 1982.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9 Found 3/4" Pipe in Mon Box.
See witness, Check Section C.
Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co. Peer Group 11-29-95

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 Replaced 3/4" Pipe with 5/8" Re-Rod and Saginaw Co. Brass Cap in existing Mon Box 12-4-95.
East 44.65 Nail & Cap Face P & T Pole
West 24.55 Nail & Cap Face P & T Pole (24.5R)
N.45°W. 37.71 Nail & Cap Face 24" Maple (38.04R)
N.45°E. 74.85 Nail & Cap Face 12" Mulberry



Signed by Ronald C. Prevost
24812

Date 12-27-95

Surveyor's Michigan License No. _____