

*Lib 7 Page 35*

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

*11/29/95. RCP*

For corners in Saginaw

Located In:

Corner Code #

*Thomas Twp.*

RECORDED & FILED  
DEC 28 12 36 PM '95  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

		12 N.	3 E.	G-10
1. Public Land Survey	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Section	S	_____	T	_____
	S	_____	T	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Ronald C. Prevost Nov. 29 95

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10 Post Set by Wampler, 1822

In 1946 point was an X in bit over concrete which was established by Hewitt McDonagh, Co. Eng. Off., on line between G-9 & G-11 and at centerline of Gratiot Rd. Pavement, 1946 distance North to G-9 was 2610.34.

L.C.R.C. L2 P55 Mon Box, 1972, Soltis  
Recorded survey L1523 P843 (exact same wits as LCRC L2 P55)  
Shown on M.D.O.T. R/W Maps.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10 Found 3/4" Pipe in Mon Box, no cover.  
Distance North to G-10 2610.33 (2610.34R) (2610.04R MDOT)  
Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co. Peer Group 11-29-95.

REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 Replaced 3/4" Pipe with 5/8" Re-rod, Saginaw Co. Brass Cap in existing Mon Box 12-4-95  
N.50°W 72.15 Ctr. Hyd.  
N.45°W. 55.70 M.D.O.T. Tag NE Face P & T Pole  
N.60°E. 108.25 M.D.O.T. Tag SE Face P & T Pole  
South 0.63 Centerline joint W bound pvt.



Signed by *Ronald C. Prevost*

Date *12-27-95*

Surveyor's Michigan License No. 24612

