

P.A. 345 OF 1990

LIBER 1956 PAGE 1127

Liber 7 Page 36

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

11/29/95 B.P.
For corners in Saginaw

Located In:

Thomas Twp.
Corner Code #

(County)

		12 N.	3 E.	H-9
1. Public Land Survey	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	R	_____
	S	_____	R	_____
3. Miscellaneous Property in Section	S	_____	R	_____
	S	_____	R	_____

REGISTER OF DEEDS
SAGINAW COUNTY MICH.

DEC 28 12 36 PM '95

RECORDED & FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Ronald C. Prevost

Nov. 29

95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-9 Post Set by Wampler, 1822
 In 1946 an old hardwood post was found by J.W. Martin (Spicer) at fence corner, fences North, South and East.
 L.C.R.C. L4, P208, 1/2" Rod, 1978, Prevost
 Recorded surveys L1523 P843, L1540 P642, L1677 P629
 Shown on M.D.O.T. R/W maps

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9 Found 1/2" Rod, see comparable witness in Section C.
 Distance North to H-8 2638.88 (2638.70 L1523 P843 Leach)
 Distance East to I-9 2614.38 (2614.44 L1523 P843 Leach)
 Is accepted as the best available evidence of the position of the original corner. Ratified by Saginaw Co. Peer Group 11-29-95

SAGINAW COUNTY
REMONUMENTATION

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 Replaced 1/2" rod with 3" x 36" Steel Pipe filled with concrete with 5/8" Saginaw Co. Brass Cap. 12-5-95.
 North 27.69 Nail & Cap E Face 20" Twin Ash (27.50 face R)
 N.01°W. 22.59 Nail & Cap W Face 24" Elm (22.33R)(21.70 Face R)
 East 16.00 Nail & Cap S Face 8" Ash
 N.88°W. 74.39 Face 3" Flowering Crab



Signed by *Ronald C. Prevost*
 Surveyor's Michigan License No. 24612

Date 12-27-95