

12-7-94 *BR*

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Libers Page 271

For corners in
Saginaw
 (County)

Located In: Corner Code ##

1. Public Land Survey SURVEY & REMONUMENTATION T 12 N. R 3 E. L1
 R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling APR 24 1995 in Section S _____ T _____ R _____
 S _____ T _____ R _____
3. Miscellaneous COMMISSION Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED & FILED
 DEC 27 9 16 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 Post by Joseph Wampler in 1822.
 W Oak 40" East 12 Lks.
 R Oak 9" S.24 1/2°W 24 Lks.
 Recorded survey 1971 L.1348, P.937 (shown on)
 LCRC 1976 L.3, P.229 Martin Mon.Box, 1/2" Rod

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-1 Found 1/2" Rod in Mon. Box & Recorded Witnesses
 East 36.30 to Mon. Box & 1/2" Rod corner I-13, T.13 N.-R.3 E.
 NW 20.23 SE corner concrete wingwall of bridge
 SW 14.47 NE corner concrete wingwall of bridge
 West 9.17 East edge metal plate on bridge

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-1 Placed 5/8" reroed & 2 1/2" Saginaw Co. Bronze Cap in existing Mon. Box in place of round 1/2" rod
 East 36.30 Mon. Box & 1/2" rod corner I-13, T.13 N.-R.3 E.
 N.45°W. 20.23 SE corner concrete wingwall bridge
 S.05°W. 14.47 NE corner concrete wingwall bridge
 West 9.16 E edge metal plate on bridge



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612