

Lib 6 Page 270

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

12-7-94 *BR*

For corners in
Saginaw

SURVEY & REMONUMENTATION

Located In: _____ Corner Code # _____

1. Public Land Survey T12 N., R. 3 E., L3
 APR 24 1995
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Contained in Section _____
 S _____ T _____ R _____
3. Miscellaneous Property in Sec. _____
 S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED & FILED
 DEC 27 9 16 AM '94
 HILTON DODD
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-3 Post by Joseph Wampler in 1822.
 Elm 14" S.28°W. 37 Lks.
 LCRC L.5, P.79, 1980 Prevost
 3/4" pipe set in river flats by Spicer Eng. (1980) on extension of the North line of Sec 10, T.12 N.-R.3 E., as used in the NE 1/4 of Sec 10 and on the distance of 2645.47 feet W from the N 1/4 corner of Sec 11, T.12 N.-R.3 E., This distance approved at by measure of evidence on the West 1/8 line in Sec 11.
 N.10°W. 36.90 face 36" Hickory, S.75°E., 205.60 face 36" Hickory

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-3 Found 3/4" pipe 1.3' deep in field (2 Hickory from L.5, P.79 gone)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-3 Placed 5/8" Rod & 2 1/2" Saginaw Co. Bronze Cap in Mon. Box in 1.5'+ below ground surface
 East 2645.47 to corner J-3
 East 1322.73 to 3/4" iron pipe 1/8 corner
 West 1325.88 to survey corner @ N line Sec 10 & centerline of River Road
 West 2691.32 to corner H-3
 South 2624.92 to corner I-4



Signed by Ronald C. Prevost Date 12-15-94

Surveyor's Michigan License No. 24612