

*Lib 7 Page 37*

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

*11/29/95* *RD*  
 For corners in Saginaw

Located In:

Corner Code #

*Thomas Twp.*

	12 N.	3 E.	I-9
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Section	S _____	T _____	R _____
	S _____	T _____	R _____

RECORDED & FILED  
 DEC 28 12 36 PM '95  
 JODAK  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4: Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5: Private Claims \_\_\_\_\_

Ronald C. Prevost

Nov. 29

95

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- I-9 Post Set by Wampler, 1822  
 L.C.R.C. L2 P2, 3/4" Pipe, 1972, McKelvey  
 L.C.R.C. L4 P149 3/4" Pipe 1/2" Rod inside, 1978, Prevost  
 Recorded survey L1523 P843  
 1/4" Iron Rod, Saginaw Co. Rd. Comm. 1983

REMONUMENTATION  
 FEB 22 1996  
 COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-9 Found 1/4" Iron Rod, see common witnesses in Section C.  
 Distance South to I-10 2596.70 (2596.90 M.D.O.T. R)  
 Is accepted as the best available evidence of the position of the original corner.  
 Ratified by Saginaw Co Peer Group 11-29-95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-9 Replaced 1/4 Rod with 3" X 36" Steel Pipe filled with concrete with 5/8" Re-Rod and Saginaw Co. Brass Cap. 12-4-95.  
 N.45°W 45.64 Ctr. Hyd. (45.59 R)  
 N.45°E. 18.88 Ctr. 4" Steel Post (18.84 R)  
 N.40°E. 19.31 Ctr. buried cable marker.  
 S.75°W. 69.32 Nail & Cap Face 12" Spruce



Signed by *Ronald C. Prevost*  
 24612

Date *12-27-95*

Surveyor's Michigan License No. \_\_\_\_\_