

APPROVED BY PEER GROUP  
P.A. 345 OF 1990  
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 45 PM '95

MICHAEL DORAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH.

For corners in

SAGINAW  
(County)

Located in:

Corner Code #/

THOMAS TOWNSHIP

- 1. Public Land Survey T 12NR 3E H-13  
T 12NR 3E I-13
- 2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_  
in Section S \_\_\_ T \_\_\_ R \_\_\_  
3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_ FEB 22 1996
- 4. Lot No. \_\_\_\_\_, Recorded Plat COMMISSION
- 5. Private Claims \_\_\_\_\_

*Liber 7 Page 13*

Register of Deeds Stamp & File Number

I, Brian D Ferguson, in a field survey on December, 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-13 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1972 in L 1 Pge 257

I-13 Wood post set by J. Wampler, Deputy Surveyor 1822.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13 Found no evidence of original government corner. Found 3/4" at location per Spicer Survey in L 1377 Pg 1195. Monument is accepted as the best available evidence of the position of the original corner.

I-13 Found no evidence of original government corner. Found 3/8" rod in rocks and glass. Monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 3" Brass Disk  
East, 27.59', Nail & cap W. fce 15" Twin Maple  
S. 60° E., 48.10', Nail & cap N fce 8x8 post  
N. 45° E., 47.46', Nail & cap E fce 18" Ash  
East, 61.67', H-1 T11N-R3E, 3" Brass Disk

I-13 3" Brass Disk in Monument Box  
East, 34.94', I-1 T11N-R3E, 3" Brass Disk  
S. 25° E., 13.03', Spike in N fce pwr pole  
N. 50° E., 7.46', PK nail NW fce pwr pole  
N. 85° W., 40.78', Nail & disk S fce pwr pole

Signed by Brian D Ferguson  
Surveyor's Michigan License No. 26454

Date 12-27-95

