

APPROVED BY PEER GROUP
 P.A. 345 OF 1990
 SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION PROJECT

LIBER 1925 PAGE 342

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Lib 6 Page 262

12-7-94 *ROD*

For corners in
Saginaw

Located In:

Corner Code #

(County) **SURVEY &**

REMONUMENTATION

- | | | | | | |
|------------------------------------|---|---|---|------|-----|
| 1. Public Land Survey | T | N | R | 3 E. | J-1 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | T | R | | |
| | S | T | R | | |
| 3. Miscellaneous Property in Sec. | S | T | R | | |
| | S | T | R | | |

APR 24 1995

COMMISSION

DEC 27 9 16 AM '94
 MILDRED M. DODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-1 Not set in Government Survey
 Information from 1941 survey work by Charles Redmond
 Corner used in 1968 Spicer Survey Work
 SCRC witnesses - 1" pipe 1974
 LCRC L.3, P.229, 3/4" pipe 1976, Martin

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 Found 2" pipe in Mon. Box
 Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Placed 5/8" Rerod & 2 1/2" Saginaw Co. Brass Cap in existing Mon. Box
 South 52.60 Nail in N. Face P Pole
 South 61.80 Center plastic cable marker
 South 2.10 Centerline of bituminous E & W
 East 26.33 P.K. nail in bituminous



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612