

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

*Sheet 6 Page 267*

For corners in

Saginaw SURVEY & Located In:

Corner Code #

(County) REMONUMENTATION

- |                                   |   |       |   |      |     |
|-----------------------------------|---|-------|---|------|-----|
| 1. Public Land Survey             | T | 12 N. | R | 3 E. | J-3 |
|                                   | T |       | R |      |     |
|                                   | T |       | R |      |     |
|                                   | T |       | R |      |     |
| 2. Property Containing in Section | S |       | T | R    |     |
| 3. Miscellaneous Property in Sec. | S |       | T | R    |     |
- APR 24 1995  
 COMMISSION
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

RECORDED & FILED  
 DEC 27 9 16 AM '94  
 MICHIGAN BOARD OF DEEDS  
 REGISTER OF DEEDS  
 SAGINAW COUNTY MICH.  
 Register of Deeds, Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3										●			
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- J-3 Post by Joseph Wampler 1822  
 Beech 5" S.20°E. 10 Lks.  
 Sugar 18" N.51°W. 8 Lks.  
 Corner shown but not witnessed in 1947 notes by Spicer Engineering Co.  
 1947 notes call for 2590.10 East to corner K-3 (Rancho Villas Plat Notes)  
 SCRC witnesses 1975 3/4" Iron 8" below bituminous  
 LCRC 1/4" rod/Mon. Box L.5, P.79, 1980 Prevost

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-3 Found 3/8" Rod/Mon. Box & recorded witnesses (L.5, P.79)  
 S.15°W. 63.95 center hydrant (S.45°E 63.39 center hydrant)  
 South 37.60 face 8" Spruce (East 37.55 set nail & cap in face 14" Spruce)  
 S.15°E. 43.30 face 6" Spruce  
 South 3'± centerline bituminous E & W  
 Found distance East to corner K-3, 2589.89 (2590.10 1947)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-3 Placed 5/8" rered & 2 1/2" Saginaw Co. Bronze Cap in existing Mon. Box in location of 3/8" rod  
 N.10°E. 8.18 set nail & cap in S face guard rail post  
 N.80°W. 16.05 set nail & cap in S face guard rail post  
 S.45°W. 63.39 center hydrant  
 South 37.55 set nail & cap in face 14" Spruce



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612