

APPROVED BY PEER GROUP
P.A. 345 OF 1990
SAGINAW COUNTY

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 27 1 46 PM '95

THE HONORABLE
REGISTER OF DEEDS
SAGINAW COUNTY MICH.

For corners in

SAGINAW
(County)

Located In:

Corner Code #/

THOMAS TOWNSHIP

- 1. Public Land Survey T 12N R 3E J-13
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Lib 7 Page 20

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat COMMISSION
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian D Ferguson, in a field survey on December 18, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13 Wood post set by J. Wampler, Deputy Surveyor 1822. LCRC recorded in 1974 in L 3 Pg 76. Corner also used as J-1 T11N-R3E

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found no evidence of original government corner. Found 3/4" iron pipe. Monument is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 3" Brass Disk in Monument Box
East, 20.75', J-1 T11N-R3E, 3" Brass Disk
East, 29.98', 3/4" Iron pipe @ ctr line Jarabec Rd
North, 32.94', Concrete monument
N. 50° E., 55.85', Nail & tag S fce pwr pole
S. 60° E., 74.88', Top ctr hydrant



Signed by Brian D Ferguson
Surveyor's Michigan License No. 26454

Date 12-27-95