

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY

LIBER 1925 PAGE 339

Lib 6 Page 265

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Saginaw SURVEY & REMONUMENTATION Located In: Corner Code ##

1. Public Land Survey APR 24 1995 T12 N. R 3 E. K-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
2. Property Controlling COMMISSION S _____ T _____ R _____
 in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED & FILED
 DEC 27 9 16 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-2 Post by Joseph Wampler, 1822
 Sugar 16" N.59°E. 23 Lks.
 Elm N.41°W. 27 Lks.
 Stone, Redmond notes 1941
 Corner used by Spicer crew 1967, no witness
 Corner dug up & raised to surface of new bit. 1969, Spicer

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found 3/4" pipe
 Distance North to K-1, (2831.3 Redmond 1941) (2831.11 Spicer 1967 & 69)(2831.36 Spicer 1994)
 Distance South to K-3, (2601.3 Redmond 1941) (2601.88 Spicer 1967 & 69) (2601.86 Spicer 1994)
 Angle K-1, K-2, K-3 East side (Spicer 1967 & 69 179°-34°)(Spicer 1994 179°-33'-55")
 Angle K-2, K-3, L-3 (Spicer 1967 & 69 90°-40'-40°)(Spicer 1994 90°-40'-00")
 Angles L-1, K-1, K-2 (Spicer 1967 & 69 88°-52°)(Spicer 1994 88°-51'-40")

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-2 Placed 5/8" Rerod with 2 1/2" Saginaw Co. Bronze Cap & Mon. Box in place of 3/4" Pipe above.
 N.75°E. 50.89 Center Chain Link Fence Post
 S.40°E 32.08 "X" on S end 36" conc. tile
 S.70°E. 22.44 "X" on N end 36" conc. tile
 N.88°E. 47.60 Face 4" Hickory



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612