

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY

LIBER 1925 PAGE 338

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Sheet 6 Page 264

For corners in
Saginaw SURVEY & REMONUMENTATION

Located In: Corner Code #/

- | | | | |
|------------------------------------|----------------|---------------|------------|
| 1. Public Land Survey | T <u>12 N.</u> | R <u>3 E.</u> | <u>K-3</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
- APR 24 1995
 COMMISSION
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECORDED & FILED
 DEC 21 9 16 AM '94
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald C. Prevost, in a field survey on December 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-3 Post by Joseph Wampler, 1822
- Ironwood 7" S.18 1/2°E. 4 Lks.
- Sugar 8" N.4°E. 14 Lks.
- Stone & 1" x 30" Pipe Redmond 1941
- SCRC witnesses 1968, 1" Pipe
- SCRC witnesses 1975, 3/4" Pipe
- SCRC witnesses 1992, 3/4" Pipe
- LCRC L.1, P.20, 1971, 3/4" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-3 Found 3/4" pipe, see common existing witnesses in Sec C below.

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-3 Replaced 3/4" Pipe with 5/8" Rerod & 2 1/2" Saginaw Co. Bronze Cap & Mon. Box set.
- S.50°W. 44.16 center hydrant (44.25 LCRC L.1, P.20)(43.75 Face Hydrant SCRC 1992)(43.70 Face Hydrant SCRC 1975)
- N.35°W. 83.05 set nail & cap Face 12" Maple
- S.10°E. 44.18 set nail & cap Face P & T Pole (44.21 SCRC, 1992)
- N.45°W. 58.85 to 3/4" Iron Property corner

Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612

