

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 **SAGINAW COUNTY REMONUMENTATION**
 SAGINAW COUNTY LIBER 1925 PAGE 337
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

12-7-94 *BO*

For corners in
 Saginaw **SURVEY & REMONUMENTATION** Located In: _____ Corner Code #/ #
 (County)
 1. Public Land Survey **T 2 N. R 3 E. K-4**
 APR 24 1995 T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Containing **COMMISSION** T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECORDED & FILED
 DEC 27 9 16 AM '94
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.
Lib 6 Page 263
 Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11	●	12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-4 Post by Joseph Wampler, 1822.
 Beech 12" S.50° W. 8 Lks.
 Beech 12" N.30½° E. 24 Lks.
 Conc. Mon. 1941 Redmond Notes.
 SCRC Witnesses 1968 1" Sq. Iron Bar.
 SCRC Witnesses 1992 1" Sq. Iron Bar.
 LCRC 1974, Leach, L.3, P.46.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-4 Found 3/4" Bar.
 N.15°W. 19.22 Ctr. C.B. Cover (LCRC L.3, P.46 N.20°W. 19.22)
 East 43.83 Ctr. Tel. Riser (SCRC 1992, E. 43.44 Face T.C.B.)
 Distance North to K-3 (Redmond 1941 2627.28) (Spicer 1994 2627.37)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Placed 5/8" Rerod with 2½" Saginaw Co. Bronze Cap & Mon. box in place of 3/4" bar.
 N.15°W. 19.22 Ctr. C.B. Cover.
 N.75°E. 42.08 Ctr. C.B. Cover.
 East 43.83 Ctr. Tel. Riser.
 S.15°E 138.00 Ctr. Hyd.
 West 34.75 Nail in Face P & T Pole



Signed by Ronald C. Prevost Date 12-15-94
 24612

Surveyor's Michigan License No. _____