

12-7-94 BOR

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw

SURVEY & Located In:

Corner Code #

(County) **REMONUMENTATION**

- | | | | | | |
|-------------------------|---|-------|---|------|-----|
| 1. Public Land Survey | T | 12 N. | R | 3 E. | K-5 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling | S | | T | | |
| in Section | S | | T | | |
| 3. Miscellaneous | S | | T | | |
| Property in Sec. | S | | T | | |

APR 24 1995

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

DEC 27 9 15 AM '94
 HILDAE M. GODAK
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

RECORDED & FILED

Lib 6 Page 262

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K-5 Post by Joseph Wampler, 1822
 W Oak 36" S.40°E. 24 Lks.
 Hickory 7" N.11 1/2°E. 6 Lks.
 12" x 12" Masonry Mon. found by Spicer Eng. crew in 1955
 LCRC 1979 Prevost L.4, P.216 12" x 12" Post
 Recorded Survey L.1681, P.395 Ferguson

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-5 Found Masonry Post, see common witness below (Sec. C)
 Distance North to K-4 2625.99 in 1955 checks in 1994

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5 Drilled hole in center of 12" x 12" Masonry Post and set 5/8" Rerod 2 1/2" Saginaw Co. Bronze Cap
 N.45°W. 45.47 Nail & Washer Face 24" Maple (LCRC, L.4, P.216, N.45°W. 45.87 10" forked Maple
 N.50°E. 33.80 Nail & Washer Face 20" Basswood
 S.35°E. 66.60 Nail & Washer Face 20" Cottonwood
 S.05°W. 13.34 Nail & Washer Face 24" Maple



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612