

APPROVED BY PEER GROUP SAGINAW COUNTY REMONUMENTATION PROJECT

P.A. 345 OF 1990

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 4 07 PM '94

MILBURN BODAK REGISTER OF DEEDS SAGINAW COUNTY MICH.

For corners in Saginaw Located In:

Corner Code #

- 1. Public Land Survey 24 1995 T 12N R 3E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- K-9
[Blank lines for corner codes]

Handwritten: Liber 6 Page 222

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, John H. Rauser, in a field survey on June 1 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (K-9) Sec. cor., Sec. 23, 24, 25 & 26, T12N-R3E
Wood post placed by J. Wampler, Deputy Surveyor, 1822
S54°W 7 lks. (4.62') 20" Maple
S79°E 16 lks. (10.56') 9" Ash
1971 Act 132 by Richard L. Sides, P.S. #13042, rec. in L. 1332, pg. 963-964, Saginaw County Records.
1972 Act 132 by Gerald R. McKelvey, P.S. #19001, rec. in L. 1372, pg. 1, Saginaw County Records. L.C.R.C. by Gerald R. McKelvey, P.S. 19004, rec. in L. 2, pg. 10, Saginaw County Records.
1974 Act 132 by Arthur H. Leach, P.S. #7236, rec. in L. 1423, pg. 714, Saginaw County Records.
1975 Act 132 by B.D. Hammond P.S. #8890, rec. in L. 1448, pg. 810, Saginaw County Records.
1978 Act 132 by John W. Martin, P.S. #4699, rec. in L. 1553, pg. 544-546 & L. 1621, pg. 336-338, Saginaw County Records.
1979 L.C.R.C. by Ronald C. Prevost, P.S. #24612, rec. in L. 4, pg. 199, Saginaw County Records.
1984 Act 132 by Duane F. Ledy, P.S. #21575, rec. in L. 1643, pg. 1164, Saginaw County Records.
1986 Recorded Plat of Plainfield Acres No. 1, rec. in L. 23, pg. 1-3, Saginaw County Records.
1989 Recorded Plat of Plainfield Acres No. 3, rec. in L. 24, pg. 1-2, Saginaw County Records

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (K-9) Sec. cor., Sec. 23, 24, 25 & 26, T12N-R3E
Found 1/2" bar in mon. box in center of South bound lane of Miller Road as per records as stated in "A" above and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (K-9) Sec. cor., Sec. 23, 24, 25, & 26, T12N-R3E
Reset 5/8" rerod w/brass cap stamped Saginaw County Monument, P.S. #39096 in existing monument box.
N32°E 61.86' Set spike w/tag #39096 in W. fce. 36" Maple
N20°E 116.06' Set PK w/tag #39096 in NW fce. Power Pole
East 32.43' Set PK w/tag #39096 in N. fce. Power Pole
N53°W 27.83' Set chis. "X" in WNW Sanitary Manhole Rim
N76°W 97.96' SE cor. brick hse. #1015 above planter box.

Signed by [Signature] Date [Signature]

Surveyor's Michigan License No. 39096

