

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT

LIBER 1925 PAGE 328

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Liber 6 Page 254

For corners in

Saginaw

(County) **SURVEY & REMONUMENTATION** Located In:

Corner Code #

- | | | |
|---------------------------------------|------------------------------|------------|
| 1. Public Land Survey | T <u>12 N.</u> R <u>3 E.</u> | <u>L-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

APR 24 1995

COMMISSION

RECORDED & FILED
 DEC 27 9 15 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-1 Not set in Government Survey
 Nail set 1967, Spicer, in line with occupation fence to South
 Boat Spike set in place of 1967 nail, Spicer 1969
 SCRC witness 1974
 LCRC L.4, P.72 Martin, 1977

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-1 Found Boat Spike in Mon. Box.
 LCRC L.4, P.72, N.15°W., 36.33 center gasline marker (N.15°W. 35.70 gasline marker 1994)
 West 6.0' to corner L-13, T.13 N.-R.3 E.

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-1 Replaced Boat Spike with 5/8" Rerod & 2 1/2" Saginaw Co. Bronze Cap in existing Mon. Box
 North 45.13 Tel Riser
 South 36.66 Face 8" Ash
 S.45°E. 46.38 gasline marker
 N.15°W. 35.70 gasline marker
 West 6.0 corner L-13, T.13 N.-R.3 E.



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612