

APPROVED BY PEER GROUP
 P.A. 345 OF 1990 SAGINAW COUNTY REMONUMENTATION PROJECT
 SAGINAW COUNTY LIBER 1925 PAGE 334

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Saginaw SURVEY & REMONUMENTATION
 (County) Located In: Corner Code #:

1. Public Land Survey **APR 24 1995** T 12 NR 3 E. L-3
 COMMISSION T _____ R _____
 T _____ R _____
 T _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECORDED & FILED
 DEC 27 9 15 AM 1994
 MICHIGAN REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Liber 6 Page 260
 Register of Deeds Stamp & File Number

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-3 Post by Joseph Wampler, 1822.
 Sugar 10" S.80½° W. 21 Lks.
 Sugar 8" N.47° E. 21 Lks.
 Co. Surveyor Harrison Cary 1879 records stones, 2 large, one over the other with 6 smaller stones around the upper large stone.
 Spicer Engineering Crew (1967) dug and found pile of stones, 3 pieces of pottery and rotted wood, set 3/4"x18" pipe in ctr. of wood, on fence line to South. Witnesses taken in 1967 are the same as recorded in L.1, P.120.
 LCRC L.1, P.120, 1971 Martin

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-3 Found 3/4" Pipe & Recorded Witnesses.
 North 30.15 Face P & T Pole, L.1, P.120 (N.30.05 N & C Face P & T pole, 1994)
 SE 74.45 Face P. Pole, L.1, P.120 (S.40°E, 74.40 N & C Face P & T pole, 1994)
 NW 61.62 Face 12" Chestnut, L.1, P.120) (N.70°W. 61.34 N & C Face 16" Chestnut, 1994)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-3 Replaced 3/4" Pipe with 5/8" Rerod with 2½" Sag. Co. Bronze Cap in Mon. Box.
 South 25.91 Center Hyd.
 North 30.05 Set Nail & Cap Face P & T Pole.
 N.70°W. 61.34 Set Nail & Cap Face 16" Chestnut.
 S.40°E. 74.40 Set Nail & Cap Face P & T Pole.



Signed by Ronald C. Prevost
 24612

Date 12-15-94

Surveyor's Michigan License No. _____