

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Sheet Page 259

For corners in

Saginaw **SURVEY & REMONUMENTATION**

Located In:

Corner Code #

1. Public Land Survey T 12 NR 3 E. L-5
 APR 24 1995 T _____
 T _____
 COMMISSION _____
 _____ R _____
 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH

DEC 27 9 15 AM '94

RECORDED & FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 Post by Joseph Wampler, 1822, W. Oak 30" is Or. Sec. Post.
 (Note: Appears a 30" W. Oak stood at 1/4 Cor. not a post.)
 Redmond, 1925, found wagon wheel spoke & bricks - Set 3/4" Pipe.
 Spicer Engineering notes show L-5 1968, 1971, 1972 & 1975.
 LCRC 1972 L.2, P.13, McKelvey 3/4" Pipe.
 Recorded Survey, Leach 1992, 3/4" Pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-5 Found 1/2" Rod and Recorded Witnesses.
 North 11.00 Nail & Disk #19001 SW side 10" Thornapple Trees (North 11.00 set N & C SW side 14" Thornapple)
 Found witness Spicer Engineering notes F.528, P. 9-20 (NE 83.09 to SW cor. brick house) (82.97 1994)
 Distance East to M-5 Redmond 1925 2617.15 (Spicer 2616.51 1994)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 Replaced 1/2" Rod with 5/8" Re-rod with 2 1/2" Sag. Co. Bronze Cap & Mon. Box.
 North 11.00 Set Nail & Cap in SW Face 14" Thornapple.
 S.10° W. 34.97 Set Nail & Cap in Face P & T Pole.
 S.20° E. 95.45 Set Nail & Cap in Face 24" Spruce.
 N.25° E. 82.97 SW Corner Brick Faced House.



Signed by Ronald C. Prevost
 24612

Date 12-15-94

Surveyor's Michigan License No. _____