

APPROVED BY PEER GROUP SAGINAW COUNTY REMONUMENTATION PROJECT

P.A. 345 OF 1990

SAGINAW COUNTY

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

DEC 14 4 07 PM '94

NICKEL... DODAR REGISTER OF DEEDS SAGINAW COUNTY MICH.

For corners in Saginaw SURVEY & Located In: REMONUMENTATION

Corner Code #

- 1. Public Land Survey APR 24 1995 T 12N R 3E COMMISSION
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

L-9

Handwritten: Liber 6 Page 221

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 and a dot in row 9, column L.

I, John H. Rauser, in a field survey on June 1 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L-9) 1/4 cor., Sec. 24 & 25, T12N-R3E Wood post placed by J. Wampler, Deputy Surveyor, 1822 N56°E 16 lks. (10.56') 14" White Oak N87°W 17 lks. (11.22') 18" Elm 1973 Winchester Park, recorded in L. 19, pg. 50 & 51, Saginaw County Records. 1976 L.C.R.C. by John W. Martin, P.S. #4699, recorded in L. 3, pg. 232, Saginaw County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L-9) 1/4 cor., Sec. 24 & 25, T12N-R3E Found no evidence of original government corner. Found 4" diam. conc. mon. in North-South fence line as per L.C.R.C. rec. in L. 3, pg. 232, Saginaw County Records. West 37.8' (R=38.05') E. face of 18" Elm R=face of 20" Elm s50°W 37.9' (R=s40°W, 37.20') E. face Westerly most 14" Oak in group of 4 R=face most Westerly 20" Maple in group of 3

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L-9) 1/4 cor., Sec. 24 & 25, T12N-R3E Set brass cap stamped Saginaw County Monument, P.S. #39096 on existing conc. monument. N80°W 38.44' Set spike w/tag #39096 in S. fce. 18" Walnut s50°W 36.03' Set spike w/tag #39096 in E. fce. 14" Quad Oak N15°E 32.33' Set spike w/tag #39096 in E. fce. 15" W. Pine s15°E 31.95' Set spike w/tag #39096 in NE. fce. 12" Twin Elm

Signed by John H. Rauser Date Jan. 1995 Surveyor's Michigan License No. 39096

