

SAGINAW COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Saginaw (County) **SURVEY & REMONUMENTATION** Located In: Corner Code # L-11

1. Public Land REMONUMENTATION N 3E  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section COMMISSION S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

APR 24 1995

DEC 29 9 29 AM '94  
MILLER & JODAK  
REGISTER OF DEEDS  
SAGINAW COUNTY MICH

RECORDED & FILED

*Leben 6 Page 282*

Register of Deeds Stamp & File Number

I, Duane F. Ledy, in a field survey on July 29, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- L-11 Set post 39.43½ chains east of K-11, J. Wampler, 1822.  
7" Ironwood S 22° W 8 links.  
9" Lynn N 15° W 25 links.  
R. Sides referenced corner in 1971, no monument information given, L1342, P595.  
J. Martin found corner in 1971, no witnesses or monument information given, L1347, P407.  
A. Leach found corner in 1973, no witnesses or monument information given, L1412, P264.  
J. Martin found 1" iron pipe (1978), L1561, P170.  
R. Prevost found 1" iron pipe (1980), L.C.R.C., L5, P86.  
No records available of perpetuation of corner before 1971.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-11 Found 1" pipe.  
Found recorded witnesses as follows:  
West 3.50' to fence corner post (3.62' to center of post, R).  
East 14.44' to nail in north face of 14" Elm (14.30' to 6" Elm, R).

Existing monument accepted as best possible position of original corner.  
Position accepted by Saginaw County Peer Review Group on December 7, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-11 Set 3" Saginaw County brass cap on 5/8" x 18" rebar over existing 1" iron pipe.  
S 80° E 10.88' to nail in S.W. face of 6" tree.  
N 85° W 3.50' to face of fence corner post.  
N 5° W 26.43' to face of fence corner post.  
East 14.44' to nail in north face of 14" Elm



Signed by *Duane F. Ledy* Date December 28, 1994  
Surveyor's Michigan License No. 21575