

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Lib 6 Page 258

For corners in

Saginaw
 (County)

Located In:

Corner Code #

SURVEY &

- | | | | | |
|------------------------------------|-----------------|---|------|-----|
| 1. Public Land | REMONUMENTATION | R | 3 E. | M-2 |
| | | T | | |
| | | T | | |
| | APR 24 1995 | T | | |
| 2. Property Controlling in Section | COMMISSION | S | T | R |
| 3. Miscellaneous Property in Sec. | | S | T | R |

RECORDED & FILED
 DEC 27 9 15 AM '94
 MICHIGAN BOARD OF LAND SURVEYORS
 REGISTER OF DEEDS
 SAGINAW COUNTY MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ronald C. Prevost, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 Post by J. Wampler in 1822.
 Ash 18" N.31°E. 21 Lks.
 Ash 7" S. 3°W. 27 Lks.
 Location By Spicer Eng. 1967 2678.0 South from M-1, in line of fence West
 Nail set by Spicer Eng. 1969 2678.0 South from M-1, in line of fence West
 3/4" Pipe set in place of nail 1972 Spicer Eng. 17.00 North of A-2, T.12 N.-R.4 E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-2 Found 3/4" Pipe
 Distance North to M-1 (Spicer Eng. 2678.0 1967 & 1969) (Spicer 2678.40 1994)
 Distance South to M-3 (Spicer Eng. 2611.66 1969) (Spicer Eng. 2612.03 1994)
 Angle M-1, M-2, M-3 West (Spicer Eng. 180°-04' 1972) (Spicer Eng. 180°-03'-50" 1994)

Is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 Replaced 3/4" Pipe with 5/8" Rerod 2 1/2" Saginaw Co. Bronze Cap & Mon. Box
 South 17.02 Corner A-2, T.12 N.-R.4 E.
 West 39.75 Center water main valve
 S.15°W. 81.13 Center hydrant
 S.20°E. 105.90 "X" on South headwall culvert



Signed by Ronald C. Prevost

Date 12-15-94

Surveyor's Michigan License No. 24612